



MOBILEPOND

A PRODUCT OF PCI MANUFACTURING, LLC

Portable, Reusable Water Storage

PCI Manufacturing's MobilePond is built according to a rigorous standard, fully inspected and tested to ensure that every weld, connection plate and paint finish is the best in the industry.

With a 30% smaller site footprint and easier mobilization and de-mobilization, the MobilePond saves you time and manpower when compared to setting up mobile frac tanks, allowing you to get your portable fluid storage units up and operating quickly. Additional savings is realized with minimal permitting, less road impact (93% fewer trucks than comparable mobile steel tanks), heating in only the most extreme temperatures and potential fines associated with leaking tank connections.

All PCI products are designed and built specifically to meet our customers' requirements in our state-of-the-art facility, with complete in-house fabrication, steel shot blast and paint departments. Complete control of the manufacturing process ensures the highest quality and consistency. Our equipment is built to provide you with a long-term investment while meeting the highest safety standards. PCI Manufacturing's low-maintenance, portable designs ensure that your investment can be used again and again.

PCI's MobilePond doesn't completely eliminate the need for the standard mobile frac tanks but can significantly reduce the number of tanks needed on site, saving valuable time and resources.

We keep our word, so you can keep yours



The PCI patent-pending MobAssist™ (pictured upper left) is highly effective when assembling the MobilePond. Unlike conventional chains, it attaches to tele-handlers and slides easily into the panel-lifting apparatus, eliminating dangers created by windy conditions and resulting in safer and faster panel installation/demobilization.

2901 North Freeway ♦ Fort Worth, Texas 76106

817-624-3181 ♦ 800-709-3184 ♦ WWW.FORTWORTHTRUCK.COM



Standard MobilePond Specifications:

- 24,000/35,000/40,000 and 48,000 bbl capacities available
- 15 to 20 modular panels—12' tall by ~27' long, weighing approximately 6100 lb
- ¼" plate steel panels
- Engineered, overlapping connection plates
- Six 4" temporary panel supports
- Six 3" bolt-down panel mating clamps
- 3" x 3" connection lugs with pins
- Unique, aluminum liner connection clamps (number varies with tank size)
- Four 4" fill pipes
- Three 4" recirculation lines with three-tier nozzles
- One 10" external (aluminum) suction line
- Two OSHA-compliant egress ladders
- Blast, external paint, customer color choice
- All hardware needed to attach accessories

Options:

PCI Manufacturing offers the options listed below, allowing customers to create a custom tank built to satisfy their specific needs.

External Manifold

- Delete standard 8" manifold
- Add 10" manifold
- Add 12" manifold
- Custom design, according to customer spec

MP MobAssist™

- Permits easy movement of panels from truck to tank installation site
- Patent-pending design easily connects to 10K-rated JLG, SkyTrak or Cat telehandlers
- Additional MobAssists available _____

Fill/Recirculation Lines

- Add 4" fill lines
- Add 6" fill lines
- Add 8" fill lines
- Custom design according to customer specs

Insulation

- 2" spray-on foam insulation, exterior of panels

Ladder

- Additional egress ladders _____
- Additional observation ladder _____

2901 North Freeway ♦ Fort Worth, Texas 76106

817-624-3181 ♦ 800-709-3184 ♦ WWW.FORTWORTHTRUCK.COM